

Projects Update



S. E.:

- ✓ 12T Dry Cryomagnet
- ✓ Syringe Pump System
- ✓ Test HT SANS Block Pressure Cells
- ✓ High Pressure Systems
- ✓ 2 kbar H₂ Pressure System
- ✓ Empty Vanadium Powder Cans
- ✓ Gas Loading System
- ✓ Reflectometry Furnace
- ✓ Training, and assistance for post-docs

Juscelino Leão

12 T Dry Cryomagnet


- Integrated 50 mK Dilution Refrigerator and GHS
- +/- 12 T symmetric vertical field
- 35mm split
- +/- 4-degree beam divergence
- Dark Angle: 40 degrees
- Dil Fridge 60+ microWatt minimum cooling power @100 mK



12T Production Plan



	Oct-20	Nov-20	Dec-20	Jan-21	Feb-21	Mar-21	Apr-21	May-21	Jun-21	Jul-21	Aug-21	Sep-21	Oct-21	Nov-21	Dec-21	Jan-22	Feb-22	Mar-22	Apr-22	May-22	Jun-22	Jul-22	Aug-22	Sep-22
Month	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Order placed	●																							
Design of magnet and cryostat	●●●	●●●●	●●●●																					
Design of DR system				●●●●	●●●●	●●●●																		
Finalisation of neutron shielding			●●	●●●●	●●●●	●●																		
Frame and integration design				●●	●●●●	●●●●																		
Compile full design and structural report						●●	●●																	
Nist Design review							●●																	
Post review discussion and modification								●●																
Preparation of component drawings and BOM						●●●●	●●●●	●●●●																
Sign off design								●●																
Machining of cryostat parts									●●●●●●	●●●●	●●●●													
Cryostat welding													●●											
Outer painting													●●											
Manufacture radiation shield														●●										
Coil winding													●●●●											
Coil reaction														●●										
Casting and finishing															●●●									
Split-pair assembly																●●●	●●							
Assembly of Cryomagnet system including Integral DR													●●●●●●	●●●●●●	●●●●●●	●●								
He-3 Required from NIST														●●										
Main system test																	●●●●							
He-3 and DR test																		●●●●						
Test contingency																			●●●●					
FAT																				●●				
Pack and Ship																					●●			
On-site comissioning																					●●●●			
Final Sign-off and payment																						●		




09/08/22 Update:

- Magnet Status:
 - The magnet wiring has been completed, and the installation of the radiation shield and outer chamber is being completed
 - These are the final steps of closing the cryostat for the preliminary test
 - System cooldown is expected for week of Sept 12th
- DR status:
 - Machining: 95% complete (ULT parts only remain)
 - Still : completed
 - 1K pot : 85% assembled
 - Mixing chamber : 50% complete
 - ULT : Sub-assemblies started
 - Heat exchangers : 80% complete



Syringe Pump System

Pneumatic Actuated High-Pressure Selector



1000 cc Pump
"Booster"




➤ TO BE DONE:

- Finish software upgrade
- Test HT seals for block cells


Many Thanks to:

- Doug Johnson
- Donna Kaltyre
- Sean Mullendore
- Colin Wrenn
- Alan Ye



Three syringe system

Syringe Pump System



Cheminert UHPLC selectors valve with Air Actuator

SPECIFICATIONS

Max press: 15,000 psi


Max temp: 50°C

Stator: SS w/inert coating

Rotor: Valcon E5

Bore: 250 micrometers

Line OD: 1/16" (NOTE: 150 microm



Digital Valve Interface



Serial Valve Interface

Syringe Pump System

Pumps "A" and "B" work in tandem


Ports "3" and "4" are plugged closed

Teledyne Pump A

A

Teledyne Pump B

B



Syringe Pump System

Pumps "A" and "B" work independently


Ports "3" and "4" are plugged closed

Teledyne Pump A

A


Teledyne Pump B

B





2 kbar H₂ Pressure System



2 kbar H₂-Pressure Vessel

- Double ended hollow cylinder autofretage design
- The design employs a “leak before burst” failure mode

To Be Done:

- Test Lil’Criter H₂-Intensifier
- Autofretage pressure vessels
- Test pressure vessels




Lil’Criter H₂-Intensifier

H ₂ Pressure Vessel Calculation						
INCONEL Alloy 625, UNS N06625/						
Tensile Strength (psi)	ID (inches)	OD (inches)	Autofretage Pressure (bar)	Autofretage Design Safety Factor	Working Pressure (bar)	Working Pressure Safety Factor
128,000	0.25	0.5	3,000	2	2,000	3.5

High Pressure Systems

Maintenance

- ✓ Pressure Rig #1
- ✓ Empty and decon pressure cells
- ✓ Training: Full pressure experiment
- ✓ Updated and tested manual
- ✓ Updated Safety paperwork
- ✓ Maintenance Pressure Rig #2
- ✓ Maintenance pressure sticks
- ✓ Inventory pressure cells and ancillary equipment



Many Thanks to:

- Sergiy Gladchenko
- Doug Johnson
- Sean Mullendore

Gas Loading Systems

Maintenance and Recalibration




- ✓ Manual Gas Loading Cart 2, 35bar
- ✓ Automated Gas Loading Cart 3, 200bar
- ✓ Manual Gas Loading Cart 1, 200bar

Inventory of sample can lid interfaces

- ✓ 20 BLCCR Rings
- ✓ 10 TLCCR lids
- ✓ 2 HT TLCCR Sticks
- ✓ 2 LT TLCCR Sticks

To Be Done:

- Test Computer Controlled cart at BT1, DCS, and HFBS for full communication



Many Thanks to:

- Donna Kaltyre
- Doug Johnson
- Sean Mullendore


Reflectometry Furnace

Vacuum/ inert gas environment
Outer aluminum window
Inner silicon window



Renewed interested motivated by users



J Feng, et.al. Surface and Coatings Technology 405,
126545 <https://doi.org/10.1016/j.surfcoat.2020.126545>



Inner alumina shielded tabletop furnace
capable of reaching 1300° C



Reflectometry Furnace




Outer aluminum window
Inner silicon window



Alumina Sample Holder and well

To Be Done:

- Finish wiring
- Test maximum temperature under argon and vacuum
- Ship to SNS for neutron testing



LIPSS/MUZAC System



Maintenance

- ✓ Replaced power supply
- ✓ Acquired extra power supply
- ✓ Training: Full pressure experiment
- ✓ Updated manual
- ✓ Updated Safety paperwork
- ✓ Separate LIPSS control
- ✓ Engineer new cells
- ✓ Upgrade cell holder
- ✓ Procure recirculating bath to replace LH45

➤ TO BE DONE:


Receive new W55 recirculating baths (Expected Nov 2022)

Supply of SANS LIPSS Pressure Vessels



Many Thanks to:

- Cedric Gagnon
- Doug Johnson
- Susana Teixeira
- Colin Wrenn
- Alan Ye



Beam Line/ Lab Equip. SOPs, User/Technical Manuals

Equipment	SOP	User Manual	Technical Manual	STATUS
Syringe Pump	✓	✓	✓	Submitted
Gas-loading	✓	✓	✓	Submitted
High Pressure	✓	✓	✓	Submitted
H2 Pressure	✓	✓	✓	Submitted
Furnaces	✓	✓	✓	Submitted
Torch	✓	✓	✓	Submitted
Spin Coater	✓	✓	✓	Submitted
2GPa Clamp Cell	✓	✓	✓	Approved
Cryogenics Training	✓	✓	✓	Approved

Current Projects Description

S. E.:

- 12T Dry Cryomagnet
- Upgrade Syringe Pump Cart for flow under pressure experiments
- Update Software for Three Syringe Pump
- Commission 2 kbar H₂ Pressure System
- Test 2 kbar H₂ Pressure Vessels
- Empty and Inventory Irradiated Powder Cans (S.E Group)
- Test HT SANS Block Pressure Cells
- Test Computer controlled cart with ICPs
- Test General Purpose 1600° C Furnace
- Finish Reflectometry Furnace for user experiment at SNS
- Receive new W55 recirculating baths (SANS/NSE)
- SANS LIPSS Pressure Vessels

Labs:

- Installation and Implementation of Glove Boxes Remote Manifold
- Training, and assistance for post-docs

Estimated Timeline

On-going to 1st quarter of 2023

Done

November 2022

Awaiting HR

Awaiting HR

On-going

October 2022

November 2022

December 2022

December 2022

November 2022

March 2023

Facility shutdown

On-going

Thank you!

Questions and/or
Suggestions for R&D for 2023

2023/2024 Shutdown Period

S. E.:

- Installation and Implementation of Glove Boxes Remote Manifold
- SANS High Temperature Furnace
- BT1 Cryo Sample Changer